



## SUMMARY TEST REPORT

FOR: Eagle Window & Door, Inc.  
2045 Kerper Boulevard  
Dubuque, Iowa 52001

Report Number: D4326.03-201-44  
Test End Date: 02/10/2014  
Report Date: 02/18/2014  
Test Record Retention End Date: 02/10/2018

SERIES TESTED: 6040 E-Series Auxiliary Window

**NAFS-11** Class CW-PG80 Size Tested 1828 x 1219 mm\* (72.0 x 48.0 in\*)-FW  
**NAFS-08** Class CW-PG80 Size Tested 1828 x 1219 mm\* (72.0 x 48.0 in\*)-FW

### Test

Resistance to Air Infiltration  
Resistance to Water Penetration  
Resistance to Structural Loading  
Forced Entry Resistance

### Results Summary

<0.01 cfm/ft<sup>2</sup> (ASTM E283)  
Pass at DP80 (ASTM E547)  
Pass at DP80 (ASTM E330)  
Pass at Grade 10 (ASTM F588)

**CAN/CGSB-82.1-M89**, Evaluation to the prescriptive requirements were not performed

### Test

Air Tightness  
Water Tightness  
Wind Load Resistance  
Blow-Out

### Rating

Fixed  
B5  
C5  
C5

### **REFERENCE:**

See ATI Report No. D4326.01-201-44 and D4326.02-201-44 for complete test results. Reference ATI Report No. A6904.01-201-44, dated 01/27/2011 for complete *Gateway* test description and test results.

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

**ARCHITECTURAL TESTING, INC**

**ARCHITECTURAL TESTING, INC**

Eric J. Schoenthaler  
Project Manager

Daniel A. Johnson  
Director - Regional Operations

849 Western Avenue North  
St. Paul, MN 55117  
Phone: 651-636-3835  
Fax: 651-636-3843  
www.archtest.com