



SUMMARY TEST REPORT

FOR: Andersen E-Series/Eagle Window & Door
2045 Kerper Boulevard
Dubuque, Iowa 52001

Report Number: F4469.02-201-44
Test End Date: 01/15/2016
Report Date: 03/04/2016
Test Record Retention End Date: 03/04/2020

SERIES TESTED: Clad Auxiliary Fixed with HMIG
MODEL TESTED: 5080

NAFS-08/-11 Class CW-PG70 Size Tested 1524 x 2438 mm (60.0 x 96.0 in.)-FW

Test

Results Summary

Resistance to Air Infiltration	<0.01 cfm/ft ² (ASTM E283)
Resistance to Water Penetration	Pass at DP70 (ASTM E547)
Resistance to Structural Loading	Pass at DP+70.0/-75.0 (ASTM E330)
Forced Entry Resistance	Pass (ASTM F 588)

ASTM E1886 / ASTM E1996

Test

Results Summary

Impact	No rips, tears or penetrations, Missile D, Zone 4
Pressure Cycling	DP +70.0/-75.0 psf

REFERENCE:

See Intertek-ATI Report No. F4469.01-201-44 and F4467.02-201-18 for complete test results.

A copy of this report will be retained by Intertek-ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

ARCHITECTURAL TESTING, INC.

ARCHITECTURAL TESTING, INC.

Eric J. Schoenthaler
Project Manager

Daniel A. Johnson
Director - Regional Operations