Architectural Testing

SUMMARY TEST REPORT

FOR: Andersen Corporation
100 Fourth Avenue North
Bayport, MN 55003

Report Number: C6514.03-201-47
Test End Date: 03/05/2013
Report Date: 03/22/2013
Test Record Retention End Date: 03/22/2017

SERIES TESTED: 400 Series Casement Window
MODEL TESTED C35 SAS DPUP IG

NAFS-08/-11

Class LC-PG70 Size Tested 71.9 x 59.9 in.
DP+70/-70

Test	**Results Summary**
Operating Ease	Pass, 18 N (4 lbf) max.
Resistance to Air Infiltration	0.01 cfm/ft^2 (ASTM E283)
Resistance to Water Penetration	Pass at DP70 (ASTM E547)
Resistance to Structural Loading	Pass at DP70 (ASTM E330)
Forced Entry Resistance	Pass (ASTM F 588)

CAN/CSA A440-00, Evaluation to the prescriptive requirements were not performed

Test	**Rating**
Operating Ease	18 N (4 lbf) max.
Air Tightness	A3
Water Tightness	B5
Wind Load Resistance	C5
Blow-Out	C5

Test	**Results Summary**
Impact	(N/A)
Pressure Cycling	(N/A)

REFERENCE:	See ATI Report No. C6514.01-201-47 and C6514.02-201-47 for complete test results.

A copy of this report will be retained by ATI for a period of four years. This report is the exclusive property of the client named herein and is applicable to the sample tested. Results obtained are tested values and do not constitute an opinion or endorsement by this laboratory.

ARCHITECTURAL TESTING, INC

Digitally Signed by: Karl Lips-Eakins

Karl A. Lips-Eakins
Senior Technician

ARCHITECTURAL TESTING, INC

Digitally Signed by: Daniel A. Johnson

Daniel A. Johnson
Director of Regional Operations

849 Western Avenue North
St. Paul, MN 55117
Phone: 651-636-3835
Fax: 717-764-4129
www.archtest.com